UNIVERSITY OF KERALA

ENGINEERING UNIT KARIYAVATTOM

Tender Shedule for the Renovation of Vehicle shed in front of the Faculty Guest House building at SH campus

SL No	Qty	Specification	Unit	Rate	Rate in words	Amount
1	110.783	od32057/2019_2020charges for dismantling the existing poly carbonate sheet roofing and truss work and stacking useful materials within a lead of 50 m as directed by the departmental authorities		35.37	Rs; Thirty Five Ps;Thirty Seven Only	3918.39
2	3	od167853/2019_2020 Labour engaged for cutting the overhanging branches of trees.	Е	1282.3	Rs; One Thousand Two Hundred Eighty Two Ps; Three zero Only	3846.90
3	911.792	10.16.1 Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	Kg	124.48	Rs; One Hundred Twenty Four Ps; Fourty Eight Only	
4	16.956	4) 10.1 Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	Kg	80.62	Rs: Eighty Ps;Sixty Two Only	1366.99

5	81.25	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-incharge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required		759.17	Rs;Seven Hundred Fifty Nine Ps; Seventeen Only	61682.56
6	34.361	13.61.1 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	sqm	108.14	Rs; One Hundred and Eight Ps; Forteen Only	3715.80
7	100	14.53.1 Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work	sqm	76.21	Rs; Seventy Six Ps; Twenty One Only	7621.00

8	50	2.28.1 Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of so	sqm	19.24	Rs:Ninteen Ps:Twenty Four	962.00			
		TOTAL					196613.52		
		PAC Rs. 196614.00/ - (Rupees One Lakh Ninty I/we agreed to execute the work			Six Thousand and Six Hundred Forteen Only) 1% above the estimate rate				
		2% below the estim			3 . At the estimate rate. 2				
	CONTRACTOR			sd/- UNIVERSITY ENGINEER					