

**UNIVERSITY OF KERALA  
ENGINEERING UNIT, KARIAVATTOM**

**Tender schedule for installation of iron grills in the Department of Psychology at Kariavattom campus.**

Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1	926.00	10.25.2 Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.	Kg	118.55	Rupees One hundred and Eighteen and paisa Fifty only	109,777.30
2	50.00	13.61.1 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	m2	108.14	Rupees One hundred and eight paisa Fourteen only	5,407.00
3	230.00	13.82.1 Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture including applying additional coats wherever required, to achieve even shade and colour. One coat	m2	68.07	Rupees Sixty Eight and paisa Seven only	15,656.10
4	130.00	14.45.1 Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade: Old work ( one or more coats)	m2	46.00	Rupees Forty Six only	5,980.00
		<b>TOTAL</b>				<b>136,820</b>
		12 % G.S.T				16,418.45
		PAC				153,238.85

PAC Rs.1,53,239/- (Rs. One Lakh Fifty Three thousand Two Hundred and Thirty Nine only)

I/We agreed to execute the work.

1. ....% above the estimate rate.

2. ....% below the estimate rate.

3. At the estimate rate.

**CONTRACTOR**

sd/-

**UNIVERSITY ENGINEER**