

**UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM**

Tender schedule for flooring and other maintenance works for Centre for Vedanta Studies in the Department of Sanskrit at Kariavattom Campus.

Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1	126.00	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).	m ²	1685.56	Rupees One Thousand Six Hundred and Eighty Five and ps Fifty Six Only	212,380.56
2	1.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand)	m ³	6848.08	Rupees Six Thousand Eight Hundred and Forty Eight and ps Eight Only	6,848.08
3	10.00	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:3 (1 cement: 3 fine sand)	m ²	326.86	Rupees Three Hundred and Twenty Six and ps Eighty Six Only	3,268.60
4	370.00	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade:One or more coats on old work	m ²	79.63	Rupees Seventy Nine and ps Sixty Three Only	29,463.10
5	74.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	m ²	73.93	Rupees Seventy Three and ps Ninety Three Only	5,470.82

6	64.00	Painting with oil type wood preservative of approved brand and manufacture: Old work (one or more coats)	m2	35.74	Rupees Thirty Five and ps Seventy four Only	2,287.36
		Total				259,718.52

PAC Rs.2,59,718/- (Rs. Two lakhs Fifty Nine Thousand Seven hundred and Eighteen only)

I/We agreed to execute the work.

1.% above the estimate rate.

2.% below the estimate rate.

3. At the estimate rate.

CONTRACTOR

UNIVERSITY ENGINEER