

University of Kerala
Engineering Unit, Kariavattom

Tender schedule for the supply and installation of Air Conditioners in the Department of Demography, Kariavattom Campus(Item rate) (Retender)

Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1	2 nos	Supply conveyance installation testing and commissioning of 2 TR 3 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22/R32 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigent, electric cable, copper pipe and thermal insulation up to 3 M as required with two year on site warranty , 5 year compressor warranty and one year free service. (Voltas/ Blue Star/Daikan/Carrier/Panasonic/Mitsubishi) 100% copper	E			
2	2 nos	Supply of 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard)with 3 months replacement guarantee and 3 year warranty	E			

3	2	nos	Supply and providing condensor stand	E			
4	4	m	Extra length of copper pipe with wire and thermal insulation	m			
			TOTAL				0.00

PAC Rs.

I/We agreed at quoted rates.

CONTRACTOR

sd/-
UNIVERSITY ENGINEER