## UNIVERSITY OF KERALA SUB DIVISION I, KARIAVATTOM

## TENDER SCHEDULE FOR LAYING RECTIFIED TILES IN VERANDAH FLOOR OF THE KERALA UNIVERSITY PRESS BUILDING

Sl No	Qty	Specification	Unit	Rate	Rate in words	Amount
Computer cabin						
1	99	<b>Od:-</b> Providing and laying vitrified tempered exterior tiles of size 300x300mm or more (thickness to be specified by the manufacture) of 1st quality conforming to IS. 15622 of approved make and colour, laid on 20mm thick cement mortar 1:4 including grouting the joints with white cement and matching	m2	1281.12	Rs. One thousand two hundred and eighty one Ps. Twelve only	126624.62
2	99	<b>15.56</b> Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	m2	45.9	Rs. Forty five Ps. Ninety	4536.71
3	3	<b>Od:</b> - Labour engaged for remooving existing floring and clearing the surface.	day	878.78	Rs. Eight hundred and seventy eight Ps. Seventyeight only	2636.34
TOTAL						133798

## Rs. 1,33,798/- (Rupees One lakhs thirty three thousand seven hundred and ninety eight only)

I/We have undertake to execute the work at	
a)% below estimate rate.	b) At estimate rate
c)% above estimate rate.	

Rate should be quoted both in figures and words

CONTRACTOR

ASSISTANT EXECUTIVE ENGINEER I