

**QUOTATION SCHEDULE FOR PROVIDING EXTERIOR TILING AND POINTING OF STONE PITCHING IN CONNECTION WITH THE  
INSTALLATION OF BOOM BARRIER AT SH CAMPUS, PALAYAM, THIRUVANANTHAPURAM**

Date of submission-10-03-2017

Time of Completion-20 days

SI No	Qty	Unit	Description of item	Unit	Rate	Rate in words	AMOUNT
1	50	m2	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	m2	883.25	Rupees eight hundred and eighty three Ps. Twenty five only	44163
2	100	m2	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Flush/ Ruled pointing	m2	224.19	Rupees two hundred and twenty four Ps ninteen only	22419.00
Grand Total							66582

Rs 66582/- ( Rupees Sixty Six thousand five hundred and eighty two only )

I/We agreed to undertake the work 1).....% above estimate rate 2) at estimate rate 3) .....% below estimate rate (Strike out which ever is not applicable)

Assisatant Engineer

Contractor