

UNIVERSITY OF KERALA							
ENGINEERING UNIT, KARIAVATTOM							
TENDER SCHEDULE FOR THE SUPPLY, INSTALLATION OF AIR CONDITIONERS FOR SETTING UP OF NANOPHOTONICS LABORATORY-PHASE III AT DEPARTMENT OF OPTO-ELECTRONICS, KARIAVATTOM CAMPUS.(ITEM RATE)							
SI No	Qty	Unit	Description of Item	unit	Rate	Rate in words	Amount
1	5	Nos.	Supply conveyance installation testing and commissioning of 1.5 TR 5 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigerent, electric cable, copper pipe and thermal insulation up to 4 Mtr as required with two year onsite warranty and five years compressor warranty. (Voltas/Bluestar/LLOYD/Daikin/General/Mitsubshi/Carrier) 100% Copper	E			

2	2	Nos.	Supply conveyance installation testing and commissioning of 1 TR5 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerant with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigerant, electric cable, copper pipe and thermal insulation up to 4 Mtr as required with two year onsite warranty and five years compressor warranty..(Voltas/Bluestar/LLOYD/Daikin/General/Mitsubshi/Carrier) 100% Copper	E			
3	2	Nos.	Supply conveyance installation testing and commissioning of 1.5 TR 5star window type Airconditioner unit with low power consumption suitable for operating on 230V, 50 HZ single phase AC Supply, required with two year onsite warranty and five years compressor warranty..(Voltas/Bluestar/LLOYD/Daikin/General/Mitsubshi/Carrier) 100% Copper	E			
4	7	Nos.	Supply of 4 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard) with 3 months replacement guarantee and 3 year warranty	E			
5	2	Nos.	Supply of 3 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard) with 3 months replacement guarantee and 3 year warranty	E			

6	10	m	Copper pipe with thermal insulation for extra length if necessary	m			
7	4	Nos.	Supply and providing condensor stand	E			
8	1	No.	Supply and providing timer suitable for 1.5TR AC unit	E			
			TOTAL			Rs.	

PAC Rs.

I/We agreed to execute the work at quoted rates.

Sd/-

CONTRACTOR

UNIVERSITY ENGINEER