

**UNIVERSITY OF KERALA  
ENGINEERING UNIT, KARIAVATTOM**

**Tender schedule for Civil works in the Department of MATHEMATICS BUILDING at Kariavattom campus utilizing RUSA funds**

SI No	Qty	Unit	Description of Item	unit	Rate	Rate in words	Amount
1	200.00	m <sup>2</sup>	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622 , of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).Size of Tile 600x600 mm.	m <sup>2</sup>	2297.89	Rs.Two thousand two hundred & ninety seven & ps. Eighty nine only	459,578.00
2	150.00	m <sup>2</sup>	Painting with silicon & acrylic emulsion based water thinnable sealer of approved brand and manufacture on wet or patchy portion of plastered surfaces One coat.	m <sup>2</sup>	100.69	Rs.One hundred & sixty nine only	15,103.50
3	60.00	m <sup>2</sup>	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work.	m <sup>2</sup>	109.12	Rs.One hundred & nine & ps. Twelve only	6,547.20
4	180.29	m <sup>2</sup>	Distempering with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work.	m <sup>2</sup>	74.29	Rs.Seventy four & ps. Twenty nine only	13,393.74
<b>TOTAL</b>					<b>Rs.</b>		<b>494,622.44</b>

**PAC Rs.4,94,622/- (Rupees Four lakh ninety four thousand six hundred & twenty two only)**

I/We agreed to execute the work. 1. ....% below the estimate rate.

2. .... % above the estimate rate. 3. At the estimate rate.

Sd/-

**CONTRACTOR**

**UNIVERSITY ENGINEER**