

**UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM**

Tender Schedule for providing split type air conditioner in the room of DNA sequencer at SICC building -Vertical extension of second floor of science block building at Kariavattom campus using RUSA funds (Item rate)						
Sl. No.	Qty	Specification	Unit	Rate	Rate in words	Amount
1	5 nos	Supply conveyance installation testing and commissioning of 2TR star rated energy efficient inverter type split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R410 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigent, electri cable, copper pipe and thermal insulation up to 4 M as required with two year on site warranty , 5 year compressor warranty and one year free service. (Voltas/ Blue Star/Daikan/Carrier/Panasonic/ Mitsubhishi) 100% copper	E			
2	5 nos	Supply of 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard)with 3 months replacement gaurantee and 3 year warranty	E			
4	5 nos	Supply and providing condenser stand	E			
5	2 nos	Supply and installation of timer suitable for 2 TR split	E			
TOTAL						

PAC Rs.

I/We agreed at quoted rates.

UNIVERSITY ENGINEER

CONTRACTOR