

**UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM**

**TENDER SCHEDULE FOR THE WORK OF AIRCONDITIONING IN THE DEPARTMENT OF PHYSICS AT KARIAVATTOM CAMPUS UTILIZING
RUSA FUNDS(ITEM RATE) (retender)**

Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1	7 nos	Supply conveyance installation testing and commissioning of 2 TR 5 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigent, electri cable, copper pipe and thermal insulation up to 4 M as required with two year on site warranty , 5 year compressor warranty and one year free service. (Voltas/ Blue Star/Daikan/Carrier) 100% copper	E			
2	7 nos	Supply of 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard)with 3 months replacement gaurantee and 3 year warranty	E			
3	7 nos	Supply and providing condensor stand	E			
4	1 nos	Supply and installation of timer suitable for 2TR split type airconditioners	E			
		Total				

PAC Rs.

I/We agreed to execute the work at quoted rates.

CONTRACTOR

Sd/-
UNIVERSITY ENGINEER