UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM

Sl. No.	Qty		Specification	Unit	Rate	Rate in words	Amount
			Tender Schedule for the Aircoditioning works of Setting up of Animal Cell in the Department of Zoology at Kariavattom campus.				
1	1	no	Supply conveyance installation testing and commissioning of 1TR 5 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigent, electri cable, copper pipe and thermal insulation up to 4 M as required with two year on site warranty , 5 year compressor warranty and one year free service. (Voltas/ Blue Star/Daikan/Carrier) 100% copper	E			
2	1	nos	Supply conveyance installation testing and commissioning of 2 TR 5 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigent, electri cable, copper pipe and thermal insulation up to 4 M as required with two year on site warranty , 5 year compressor warranty and one year free service. (Voltas/ Blue Star/Daikan/Carrier) 100% copper	E			

				E				
3	1	no	Supply of 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard)with 3 months replacement gaurantee and 3 year warranty	E				
4	1	no	Supply of 3 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard/ similar made)with 3 months replacement gaurantee and 3 year warranty	E				
5	2	m	Extra copper pipe with wire and thermal insulation	m				
			TOTAL					

PAC Rs.

I/We agreed at quoted rates.

UNIVERSITY ENGINEER   **CONTRACTOR**