

UNIVERSITY OF KERALA

ENGINEERING UNIT KARIYAVATTOM

**Tender Shedule for the work of Re-laying of dismantled tiles from the platinum jubilee indoor court at SH Campus to
GV Raja Gymnasium, Women fitness centre and Health Club at Kariavattom**

SL NO	Qty	Specificaations	Unite	Rate	Rate in Words	Amount
		Gymnasium and Fitness Centre				
1	385	15.23.10 Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	sqm	43.52	Rs; Fourty Three Ps;Fifty Two Only	16755.20
2	385	od35990/2018_2019 Conveying and laying departmental rubberised floor tiles of size 504x504 mm in floors as per departmental direction using synthetic adhesive or other suitable adhesive as per manufacturers specification.	sqm	333.23	Rs; Three Hundred Thirty Three Ps;Twenty Three Only	128293.55
		Women's fitness centre and health club at Kariyavattom				
3	265	od175505/2019_2020 Cleaning the cement floor by brooming thoroughly, washing and removing all dirt and loose particle from the floor, making it ready for receiving new rubber flooring etc complete as per departmental store	sqm	117.91	Rs; One Hundred Seventeen Ps; Ninty One Only	31246.15

4	265	od35990/2018_2019 Conveying and laying departmental rubberised floor tiles of size 504x504 mm in floors as per departmental direction using synthetic adhesive or other suitable adhesive as per manufacturers specification	sqm	333.23	Rs; Three Hundred Thirty Three Ps;Twenty Three Only	88305.95
		TOTAL				264600.85
		Rs 264601/-- (Rupees Two lakh Sixty Four thousand and Six Hundred one only)				
<p>I/we agreed to execute the work.</p> <p>1.....% above the estimate rate</p> <p>2.....% below the estimate rate</p> <p>3. At the estimate rate.</p>						
CONTRACTOR			sd/- UNIVERSITY ENGINEER			