

UNIVERSITY OF KERALA						
ENGINEERING UNIT, KARIAVATTOM						
Tender schedule for Providing infrastructure facilities for setting up of two computer labs at KUOTE Kumarapuram						
Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1.00	110.00	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	m ²	29.41	Rs.Twenty Nine & ps. Forty One only	3,235.10
2.00	115.00	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete.Size of Tile 600x600 mm	m ²	2062.11	Rs.TwoThousand & Sixty two & ps. Eleven only	237,142.65
3.00	240.00	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade :One or more coats on old work	m ²	77.00	Rs.Seventy Seven only	18,480.00
4.00	30.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :	m ²	71.13	Rs.Seventy One ps. Thirteen only	2,133.90

5.00	17.00	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete :125 mm	E	42.39	Rs.Forty Two ps. Thirty Nine only	720.63
6.00	10.00	Providing and fixing oxidised M.S. casement stays (straight peg type) with necessary screws etc. complete. 300 mm weighing not less than 200 gms	E	53.09	RsFifty Three ps. Nine only	530.90
7.00	0.50	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of thickness 4 mm	m ²	1013.05	Rs.One Thousand & Thirteen & ps. Five only	506.53
		Total				262,749.71

PAC Rs.2,62,750/- (Rs. Two Lakh Sixty Two thousand Seven hundred & Fifty only)

I/We agreed to execute the work. 1.% above the estimate rate.

2.% below the estimate rate. 3. At the estimate rate.

sd/-

CONTRACTOR

UNIVERSITY ENGINEER