

**University of Kerala  
Engineering Unit, Kariavattom**

**QUOTATION SCHEDULE FOR THE WORK OF SUPPLY AND INSTALLATION OF SUBMERSIBLE PUMPSET AT NEWLY CONSTRUCTED OPEN WELL NEAR HYMAVATHY PUMP HOUSE AT KARIAVATTOM CAMPUS**

Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
	1 no	Supply conveyance installation testing and commissioning of 3 phase 50 HZ 10 HP OPEN WELL Submersible pump horizontal type cast iron body 30 M to 52 M head range 12 litres/sec to 18 litres/sec flow rate complete with all accessories etc as required ( KIRLOSKAR/TEXMO)	E			
	1 no	Supply conveyance installation testing and commissioning of 3 phase 50 HZ 10 HP Fully AutomATIC Star Delta starter with single phase preventer in the existing feeder pillar box using suitable size bolts and nuts with washers and giving connections etc as required (L&T/ BCH)	E			
		<b>Total Rs</b>				

**PAC Rs.**

i/We agreed to quoted rate.

**CONTRACTOR**

sd/-  
**UNIVERSITY ENGINEER**