

**UNIVERSITY OF KERALA  
ENGINEERING UNIT**

**TENDER SCHEDULE FOR THE WORK OF PROVIDING ANTI-SKID VITRIFIED TILE FLOORING TO THE CLASS ROOMS**

**IN THE KARIAVATTOM CAMPUS NURSERY SCHOOL.**

Sl.No.	Specification	Quantity	Unit	Rate	Rate in words	Amount
1	Labour engaged for cleaning the room and rearranging furniture etc coolie	2	E	545.93	Rs.Five hundred & Forty five & ps.Ninety three only	1,091.86
2	Providing and laying anti skid Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622 , of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6mm thickness, including grouting of joints (Payment for grouting of jointsto be made separately). Size of Tile 600x600 mm	135	m <sup>2</sup>	2238.26	Rs.Two thousand two hundred & thirty eight & ps. Twenty six only	302,165.10
<b>TOTAL</b>						<b>303,256.96</b>

**PAC Rs 3,03,257/- (Rupees Three lakhs Three thousand Two Hundred and Fifty Seven Only)**

I/We agreed to execute the work.

1. ....% above the estimate rate.

2. ....% below the estimate rate

3. At the estimate rate

**CONTRACTOR**

Sd/-  
**UNIVERSITY ENGINEER.**