

**UNIVERSITY OF KERALA
ENGINEERING UNIT**

TENDER SCHEDULE FOR AIRCONDITIONING WORKS IN ROOM NO. 49 & 22 OF THE DEPARTMENT OF PHYSICS AT

KARIAVATTOM CAMPUS.(ITEM RATE)

Sl.No.	Specification	Quantity	Unit	Rate	Rate in words	Amount
1	Supply conveyance installation testing and commissioning of 2 TR 3 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigent, electri cable, copper pipe and thermal insulation up to 4 M as required with one year warranty and one year free service. (Voltas/ Blue Star/Darkon/Carrier)100% copper	6.00	E			
2	Supply of 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard) with 3 months replacement guarentee and 3 year warrenty	6.00	E			

PAC RS.

I/We agreed at quoted rates.