

**UNIVERSITY OF KERALA
ENGINEERING UNIT KARIAVATTOM**

| Tender Schedule for Providing Air conditioners in the Seminar hall at Department of Geology at Kariavattom Campus(Item Rate) | | | | | | | |
|---|-----|-----|--|------|------|---------------|--------|
| SI No | Qty | | Specification | Unit | Rate | Rate in words | Amount |
| 1 | 4 | nos | Supply conveyance installation testing and commissioning of 2 TR 5 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigent, electric cable, copper pipe and thermal insulation up to 4 Mtr as required with two year onsite warranty and five years compressor warranty. (Voltas/BlueStar/Daikin/Carrier) 100% Copper | E | | | |
| 2 | 4 | nos | Supply of 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard/ similar made) with 3 months replacement gaurantee and 3 year warranty | E | | | |
| 3 | 2 | m | Extra length of copper pipe with wire and thermal insulation | m | | | |
| 4 | 4 | nos | Supply and providing condensor stand | E | | | |
| | | | TOTAL | | | | |

PAC RS.

I/We agreed to quoted rate.

CONTRACTOR

Sd/-
UNIVERSITY ENGINEER