

**UNIVERSITY OF KERALA**

**ENGINEERING UNIT, KARIAVATTOM**

**TENDER SCHEDULE FOR THE SUPPLY AND INSTALLATION OF SPLIT TYPE AIR CONDITIONERS FOR MULTIPLEX AT SCHOOL OF DISTANCE  
EDUCATION SH CAMPUS (ITEM RATE)**

SI No	Qty	Unit	Description of Item	unit	Rate	Rate in words	Amount
1	5	Nos.	Supply conveyance installation testing and commissioning of 1.5 TR 3 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigerent, electric cable, copper pipe and thermal insulation up to 4 Mtr as required with two year onsite warranty and five years compressor warranty. (Voltas/Bluestar/Daikin/Carrier) 100% Copper	E			
2	5	Nos.	Supply of 4 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V ( V-Guard )with 3 months replacement gaurantee and 3 year warranty	E			
3	5	Nos.	Supply and providing condensor stand	E			
			<b>TOTAL</b>			<b>Rs.</b>	

**PAC Rs.**

I/We agreed to execute the work at quoted rates.

**CONTRACTOR**

**Sd/-**

**UNIVERSITY ENGINEER**