

**University of Kerala**  
**Engineering Unit, Kariavattom**

**Tender Schedule for the work of setting up of a modern green house in the Department of Geology at Kariavattom campus.**

	Quantity	Specification	Unit	Rate	Rate in words	Amount
1	200	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift upto 1.5 m. All kinds of soil	m <sup>2</sup>	21.06	Rs.Twenty one & ps. Six only	4212
2	320	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	m <sup>3</sup>	10.86	Rs.Ten & ps. Eighty Six only	3475.2
3	16	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand (zone-III): 6 graded stone aggregate 40 mm nominal size)	m <sup>2</sup>	7269.00	Rs.Seven thousand Two hundred & Sixty Nine only	116304
4	7	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Foundations, footings, bases of columns, etc. for mass concrete	m <sup>2</sup>	292.83	Rs.Two Hundred and Ninety Two & ps. Eighty Three only	2049.81

5	160	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:3 (1 cement: 3 fine sand)	m <sup>2</sup>	342.43	Rs.Three Hundred and Forty Two & ps. Forty Three only	54788.8
		Total				<b>180829.81</b>

**PAC Rs.1,80,830/- (Rs.One lakh Eighty thousand Eight hundred & Thirty only**

I/We agreed to execute the work.

1. ....% above the estimate rate.

2. ....% below the estimate rate.

3. At the estimate rate.

**CONTRACTOR**

**sd/-**  
**UNIVERSITY ENGINEER**