

**UNIVERSITY OF KERALA****ENGINEERING UNIT, SUBDIVISION No-1****Quotation Scheduled for RF sputtering lab in the Department of Opto Electronics University Of Kerala at Kariyavattom Campus****Date of submission:- 05/03/2026****Time of Completion :- 15 days**

SL No	Quantity	Description	Unit	Rate	Rate in Words	Amount
1	19	Dismantling aluminium / Gypsum partitions, doors, windows, fixed glazing and falseceiling including disposal of unserviceable material and stacking of serviceable material with in 50 metres lead as directed by Engineer - in-charge	M2	59.64	Rs Fifty Nine Ps; Sixty Four only	1133.16
2	7.2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	M2	57.76	Rs Fifty Seven Ps Seventy Six only	415.87
3	0.6	Providing and laying in position cement concrete 1:2:4 ( 1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) up to floor five level excluding the cost of centering, shuttering, finishing for leveling coarse of floor and roof etc.	M3	9418.05	Rs Nine Thousand Four Hundred Eighteen Ps;zero Five only	5650.83
4	7.2	Plastering with cement mortar 1:3 12mm thick finished with a floating coat of neat cement moxing with Dr. Fixit (101 LW+ pidiproof) complete as per the direction of Engineer	M2	524.94	Rs Five Hundred Twenty Four Ps; Ninty Four only	3779.57
5	22	Removing of wall paint by scrapping, along with removal of fungal growth on wallsurfaces and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	M2	20.94	Rs Twenty Ps : Ninty Four only	460.68
6	22	Applying stain block primer of approved make and quality to the ceiling or wall with one or more coat to remove the stains. The surface should be cleaned thoroughly before applying the primer	M2	113.47	Rs One Hundred Thirteen Ps fourty Seven only	2496.34

7	22	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	M2	82.65	Rs Eighty Two Ps Sixty Five only	1818.30
8	124.6	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade:One or more coats on old work	M2	116.47	Rs One Hundred Sixteen Ps Fourty Seven only	14512.16
9	11.4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :One or more coats on old work	M2	110.97	Rs One Hundred Ten Ps Ninty Seven only	1265.06
10	25	Providing and fixing sheet covering over expansion joints with iron screws as per design.Aluminium fluted strips 3.15 mm thick 300 mm wide (from spec 5.29.2.1)	Mtr	835.07	Rs Eight Hundred Thirty Five Ps zero Seven only	20876.75
11	40	Providing and fixing false ceiling with e board classic tile or equivalent make of size 610x610x4 mm ceiling of approved quality in aluminium frame work with necessary screws etc complete ( aluminium frame work shall be paid separately)	M2	801.25	Rs Eight Hundred Zero One Ps Twenty Five Only	32050.00
		Total				84458.72
		round off Total				84459/-

Rupees Eighty four thousand Four Hundred and Fifty Nine Only  
I/We undertake to execute the work at 1.....% below estimate rate

2) At the estimate rate      3) ..... Above the estimate rate

CONTRACTOR (Name and Address)

ASSISTANT EXECUTIVE ENGINEER



|