

Schedule

UNIVERSITY OF KERALA						
SUB DIVISION I, KARIYAVATTOM						
Quotation schedule for the Publication sales counter in the University Library- Maintenance of toilet						
Date of Submission :- 16/07/2025				Time of duration :- 10 days		
Sl No	Quantity	Description of item	Unit	Rate	Rate in words	Amount
1	3.600	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	M2	77.55	Seventy seven Rupees and fifty five paise only	279.18
2	0.160	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	M3	2572.86	Two thousand five hundred and seventy two Rupees and eighty six paise only	411.66
3	1.000	Dismantling water closet Indian/European type and disposal of the debris 150 m out side the area as per Dept direction	Each	490.60	Four hundred and ninety Rupees and sixty paise only	490.60
4	0.160	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil	M3	263.35	Two hundred and sixty three Rupees and thirty five paise only	42.14

Schedule

5	5.000	Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of Joints complete as per direction of engineer in charge.110 mm dia 6Kgf/cm2	M	591.37	Five hundred and ninety one Rupees and thirty seven paise only	2956.85
6	3.000	Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 110 mm dia Elbow	Each	114.21	One hundred and forty Rupees and twenty one paise only	342.63
7	1.000	Providing and fixing PVC moulded fittings/accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 110x110x110 mm dia Door tee	Each	194.48	One hundred and ninety four Rupees and forty eighty paise only	194.48
8	0.285	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	M3	9441.22	Nine thousand four hundred and forty one Rupees and twenty two paise only	2690.75
9	3.000	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer- in- Charge 25 mm dia 12 Kgf/cm2 - Internal work - Exposed on wall	M	319.85	Three hundred and nineteen Rupees and eighty five paise only	959.55
10	3.000	Providing and fixing PVC mouded/ accessories for rigid PVC pipe, including jointing with PVC solvent cement - 15x25mm pn 16 elbow	Each	101.11	One hundred and one Rupees and eleven paise only	303.33

Schedule

11	1.920	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of Ist quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 cement : 4 Coarse sand), including pointing the joints with white cement and matching pigments etc., complete.	M2	1419.10	One thousand four hundred and nineteen Rupees and ten paise only	2724.67
12	1.680	Providing and fixing I st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer -in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	M2	1363.20	One thousand three hundred and sixty three Rupees and twenty paise only	2290.18
13	1.000	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: W.C. pan with ISI marked white solid plastic seat and lid	Each	7102.28	Seven thousand one hundred and two Rupees and twenty eight paise only	7102.28

Schedule

14	2.000	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS: 8931 15 mm nominal bore	Each	641.41	Six hundred and forty one Rupees and forty one paise only	1282.82
15	2.000	Providing and fixing uplasticised PVC connection pipe with brass unions: 45 cm length	Each	109.19	One hundred and nine Rupees and nineteen paise only	218.38
16	1.000	Supplying and fixing CP Health faucet good quality including cost of materials and labour charges etc. complete as per the direction of site engineer-in-charge.	Each	758.61	Seven hundred and fifty eight Rupees and sixty one paise only	758.61
17	1.000	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	Each	908.11	Nine hundred and eight Rupees and eleven paise only	908.11
Total Amount						23956
Rs 23,956 /- (Rupees :- Twenty three thousand nine hundred and fifty six only)						
I/We agreed to executive the work at 1).....% below estimate rate, 2) At estimate rate , 3).....% above estimate rate						
CONTRACTOR			ASSISTANT EXECUTIVE ENGINEER			

Name :-

Address :-