

**UNIVERSITY OF KERALA****ENGINEERING UNIT, SUBDIVISION II, KARIAVATTOM**

**Quotation schedule for urgent work for replacing existing fixed wooden window shutters with weld mesh for proper ventilation in two floors at staircase area in department of Kerala Studies, Kariavattom.**

**Date of submission : 11/08/2025****Time of Completion : 25 days**

SL No	Description	Quantity	Unit	Rate	Rate in Words	Amount
1	10.16.1 Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.Hot finished welded type tubes.	34.00	kg	198.59	Rs One Hundred and ninety eight Ps fifty nine only	6752.06
2	OD53652/2025-2026 Providing and fixing 2mm dia. GI weld mesh wire of size 16mmx16mm including cutting to required size and shape, straightening and fixing with wire nails/spot welding etc. complete as per the direction of the Engineer	10.00	sqm	679.34	Rs Six Hundred and seventy nine Ps thirty four only	6793.40
3	13.61.1 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	10.00	sqm	168.52	Rs One Hundred and Sixty eight Ps Fifty two only	1685.20
4	Labour (carpenter) engaged removing wooden window shutters (1.20 x 0.50 m) in each floor for fixing weld mesh complete	4.00	each	1224.56	Rs One Thousand Two Hundred Twenty Four Ps Fifty six only	4898.24

5	14.72 Providing and fixing double scaffolding system (cup lock type) on the exterior side, upto seven story high made with 40 mm dia. M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challoes, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required location with essential safety features for the workmen etc. complete as per directions and approval of Engineer- in Charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding. Note:- This item to be used for maintenance work judiciously, necessary deduction for scaffolding in the existing item to be done .	42.00	sqm	365.33	Rs Three Hundred and sixty five Ps thirty three only	15343.86
<b>Total Amount</b>						<b>35472.76</b>
After round off Total (Rs.39,700/- Thirty nine Thousand and Seven Hundred Only )						<b>35473.00</b>

I/We undertake to execute the work at 1).....% below estimate rate

2) At the estimate rate

3) ..... Above the estimate rate

CONTRACTOR (Name and Address)

Sd/-  
ASSISTANT EXECUTIVE ENGINEER