

Schedule

UNIVERSITY OF KERALA						
SUB DIVISION I, KARIYAVATTOM						
Quotation schedule -Re Construction of damaged drain behind the University press building at SH Campus						
Date of Submission :- 08/08/2025				Time of duration :- 20 days		
SI No	Quantity	Description of item	Unit	Rate	Rate in words	Amount
1	1.770	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge.	M3	1730.20	One thousand seven hundred and thirty Rupees and twenty paise only	3062.45
2	1.600	Demolishing stone rubble masonry manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer -in- Charges: In cement mortar	M3	2064.97	Two thousand and sixty four Rupees and ninety seven paise only	3303.95
3	4.060	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	M3	8588.47	Eight thousand five hundred and eighty eight Rupees and forty seven paise only	34869.19
4	12.000	Centering and shuttering including strutting, etc. and removal of form for: Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	M2	717.20	Seven hundred and seventeen Rupees and twenty paise only	8606.40

Schedule

5	284.200	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	Kg	98.30	Ninety eight Rupees and thirty paise only	27936.86
6	17.500	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 cement : 4 fine sand)	M2	386.36	Three hundred and eighty six Rupees and thirty six paise only	6761.30
Total Amount						84540
Rs 84,540 /- (Rupees :- Eighty four thousand five hundred and forty only)						
I/We agreed to executive the work at 1).....% below estimate rate, 2) At estimate rate , 3).....% above estimate rate						
<div style="display: flex; justify-content: space-between;"> <div>CONTRACTOR</div> <div>ASSISTANT EXECUTIVE ENGINEER</div> </div>						

Name :-

Address :-