

Schedule

UNIVERSITY OF KERALA						
SUB DIVISION I, KARIYAVATTOM						
Quotation schedule for the Urgent repair work of entrance near back gate at SH Campus Palayam						
Date of Submission :- 07/07/2025				Time of duration :- 10 days		
SI No	Quantity	Description of item	Unit	Rate	Rate in words	Amount
1	40.00	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles above 25 mm and up to 40 mm	M2	119.72	One hundred and nineteen Rupees and seventy two paise only	4788.80
2	0.50	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	M3	8109.18	Eight thousand one hundred and nine Rupees and eighteen paise only	4054.59
3	6.050	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	M3	9441.22	Nine thousand four hundred and forty one Rupees and twenty two five paise only	57119.38
Total Amount						65963
Rs 65,963 /- (Rupees :- Sixty five thousand nine hundred and sixty three only )						
I/We agreed to executive the work at 1).....% below estimate rate, 2) At estimate rate , 3).....% above estimate rate						
<b>CONTRACTOR</b>			<b>ASSISTANT EXECUTIVE ENGINEER</b>			

Name :-

Address :-