

**UNIVERSITY OF KERALA**

**ENGINEERING UNIT, KARIAVATTOM**

**Quotation schedule for Reconstruction of collapsed compound wall in front of the University Campus, Kariavattom from Golden Jubilee building to Men's hostel compound- Replacing of dismantled grill portion with solid block masonry.**

**Date of submission :**

**Time of Completion : 30 days**

SL No	Description	Quantity	Unit	Rate	Rate in Words	Amount
<b>1</b>	<b>Grill portion</b>					
1.01	15.56 Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	6.00	sqm	57.76	Rs Fifty Seven Ps Seventy Six only	346.56
1.02	4.2.5 Providing and laying cement concrete in retaining walls, return walls, walls ( any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc. up to floor five level, excluding the cost of centering, shuttering and finishing: 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	0.70	cum	11336.23	Rs Eleven thousand Three Hundred and Thirty six Ps Twenty three only	7935.36
1.03	50.6.1.8 Solid block masonry using pre cast solid blocks (Factory made) of size 40x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level with thickness 15cm in: CM 1:6 ( 1 cement : 6 coarse sand etc complete	0.40	cum	7791.91	Rs Seven Thousand Seven Hundred and Ninety one Ps Ninety one only	3116.76
1.04	13.1.1 12 mm cement plaster of mix:1:4 ( 1 cement : 4 fine sand)	6.20	sqm	377.98	Rs Three Hundred and seventy seven Ps Ninety eight only	2343.48

1.05	OD160987/2025-2026 Embedding concrete iron nails of size 2 inch in cement concrete and finishing with 1:2 cement mortar including all material and labour charges (rate of concrete to be paid separately)	5.00	sqm	456.34	Rs Four Hundred and Fifty six Ps Thirty Four only	2281.70
1.06	13.46.1 Finishing walls with Acrylic Smooth exterior paint of required shade:New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	12.00	sqm	213.92	Rs Two Hundred and Thirteen Ps Ninety two only	2567.04
<b>Total Amount</b>						<b>18590.90</b>
<b>After round off Total (Rs.18,591/- Eighteen Thousand Five Hundred and Ninety one Only )</b>						<b>18591.00</b>

I/We undertake to execute the work at 1).....% below estimate rate

2) At the estimate rate

3) ..... Above the estimate rate

CONTRACTOR (Name and Address)

Sd/-  
ASSISTANT EXECUTIVE ENGINEER



|