

UNIVERSITY OF KERALA

ENGINEERING UNIT, KARIAVATTOM

Quotation schedule for urgent work for closing main entrance to building for Department of Arabic along with minor repair work at Manonmaniam Sundaranar International centre for Dravidian cultural studies at Kariavattom .

Date of submission :

Time of Completion : 25 days

SL No	Description	Quantity	Unit	Rate	Rate in Words	Amount
1	Closing entrance					
1.01	10.26.1 Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer.M.S. tube	142.00	kg	201.47	Rs Two Hundred and One Ps Forty Seven only	28608.74
1.02	13.61.1 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	11.00	sqm	168.52	Rs One Hundred and Sixty eight Ps Fifty two only	1853.72
1.03	OD107576/2025-2026 Labour (mason) engaged for cutting opening in existing masonry wall after ascertaining slope for providing new rain water pipe as per the direction of the Engineer	1.00	each	1224.56	Rs One Thousand Two Hundred Twenty Four Ps Fifty six only	1224.56
1.04	50.4.1.1 Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) up to floor five level excluding the cost of centering, shuttering, finishing for leveling coarse of floor and roof etc.	0.06	cum	9341.74	Rs Nine Thousand Three Hundred and Forty one Ps Seventy four only	560.50

1.05	11.41.2 Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS :15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4(1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete.Size of Tile 600 x 600 mm.	2.00	sqm	1815.97	Rs One Thousand Eight Hundred and Fifteen Ps Ninety seven only	3631.94
1.06	50.18.9.17.2 Providing and fixing PVC pipes including fixing the pipe with clamps/clips at 1.00 m spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 63 mm dia 4 Kgf/cm ² - External work - exposed on wall	1.50	metre	251.95	Rs Two Hundred and Fifty one Ninety Five only Ps	377.93
1.07	50.18.9.20.4 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes,including jointing with PVC solvent cement - 63 mm dia Bend	1.00	no	85.19	Rs Eighty Five Ps Nineteen only	85.19
1.08	13.98.1 Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade:One or more coats on old work	10.00	sqm	116.47	Rs One Hundred and sixteen Ps Forty seven only	1164.70
Total Amount						37507.28
After round off Total (Rs.37,507/- Thirty seven Thousand Five Hundred and Seven Only)						37507.00

I/We undertake to execute the work at 1).....% below estimate rate

2) At the estimate rate

3) Above the estimate rate

CONTRACTOR (Name and Address)

Sd/-
ASSISTANT EXECUTIVE ENGINEER