

UNIVERSITY OF KERALA**ENGINEERING UNIT****Quotation schedule for Urgent repair work of pillar near the exit gate at SH Campus, Palayam .****Date of submission- 03/10/2026****Time of Completion -: 7 days**

SL No	Quantity	Description	Unit	Rate	Rate in Words	Amount
1	75	10.1 Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	119.28	Rs One Hundred and Nineteen Ps Twety Eight only	8946.00
2	12	Providing and fixing carbon steel galvanised (minimum coating 5 micron) dash fastener of 16 mm dia double threaded 6.8 grade (yield strength 480 N/mm2), counter sunk head, 6 grade sleeve, including drilling of hole in frame, concrete/masonry, etc. as per direction of Engineer-in-charge.	Each	245.68	Rs Two Hundred and Fouty Five Ps Sixty Eight Only	2948.16

3	4	13.50.3 Applying priming coat:With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron /steel works	M2	71.16	Rs Seventy One Ps Sixteen only	284.64
4	1	OD162678/2026-2027 Epoxy Bonding agent design to adhere concrete to steel	Kg	2018.80	Rs Two Thousand and Eighteen Ps Eighteen only	2018.80
5	0.240	OD162661/2026-2027 Micro-concrete of strength not less than 60 N/mm2 using 10mm down aggregates for retrofitting pillar	M3	62616.53	Rs Sixty Two Thousand and Six Hundred sixteen Ps: Fifty Three Only	15027.97
6	4	5.9.6 Centering and shuttering including strutting, etc. and removal of form for:Columns, Pillars, Piers, Abutments, Posts and Struts	M2	1030.96	Rs One Thousand and Thirty Ps Ninety Six Only	4123.84
7	1	4.1.2 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:1 1/2:3 (1 Cement: 1 1/2 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	M3	9977.73	Rs Nine Thousand Nine Hundred Seventy Seven Ps Seventy Three Only	9977.73

8	5	13.46.1 Finishing walls with Acrylic Smooth exterior paint of required shade:New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	M2	213.92	Rs Two Hundred Thirteen Ps Ninety Two Only	1069.60
9	12	13.98.1 Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade:One or more coats on old work	M2	116.47	Rs One hundred and Sixteen Ps Fourty Seven Only	1397.64
		Total				45794.38
		After round off Total				45794/-

I/We undertake to execute the work at 1.....% below estimate rate

2) At the estimate rate

3) Above the estimate rate

CONTRACTOR (Name and Address)

Sd/-
Assistant Executive Engineer (i/c)