| Sch | nedr | ıle |
|------|------|-----|
| DUI. | icut | 11C |

UNIVERSITY OF KERALA SUB DIVISION I, KARIYAVATTOM

Quotation schedule for the Urgent Maintenance Work at Kitchen and Work Area of Women's Hostel Thycaud- Reg.

| Date of Submission :- 10/07/2025 | | Time of duration :- 30 days | | | | |
|----------------------------------|----------|---|------|---------|--|----------|
| SI No | Quantity | Description of item | Unit | Rate | Rate in words | Amount |
| 1 | 1.053 | Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar | M3 | 2177.17 | Two thousand one hundred and seventy seven Rupees and seventeen paise only | 2292.56 |
| 2 | 1.134 | Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge. Nominal concrete 1:4:8 leaner mix (including equivalent design mix) | M3 | 1588.97 | One thousand five hundred and eighty eight Rupees and ninety seven paise only | 1801.89 |
| 3 | 2.122 | Demolishing R.C.C. work manually / by mechanical means including stacking of steel bars and disposal of unserviceable material with in 50 metres lead as per direction of Engineer -in-Charge. | M3 | 3753.49 | Three thousand seven hundred and fifty three Rupees and forty nine paise only | 7964.91 |
| 4 | 1.500 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size) | | 9441.22 | nine thousand four hundred and forty one Rupees and twenty two paise only | 14161.83 |

| | | Sched | ule | | | |
|---|---------|--|-----|--------|--|----------|
| 5 | 12.000 | 12 mm cement plaster finished with a floating coat of neat cement of mix:1:4 (1 cement : 4 fine sand) | M2 | 463.12 | Four hundred and sixty three Rupees and twelve paise only | 5557.44 |
| 6 | 155.740 | Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. | Kg | 143.81 | One hundred and forty three Rupees and eighty one paise only | 22396.97 |
| 7 | 12.400 | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work | M2 | 168.52 | One hundred and sixty eight Rupees and fifty two paise only | 2089.65 |
| 8 | 20.400 | Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. | M2 | 860.86 | Eight hundred and sixty Rupees and eighty six paise only | 17561.54 |

| | | Schedu | le | | | |
|---|---|---|----------|-------------|---|---------|
| 9 | 7.000 | Providing ridges or hips width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.80 mm thick with zinc coating not less than 275 gm/m2 | М | 1053.88 | One thousand and fifty three Rupees and eighty eight paise only | 7377.16 |
| | | Total Amount | | | | 81204 |
| | | Rs 81,204 /- (Rupees :- Eighty one thou | usand tw | o hundred a | nd four only) | |
| | I/We agreed to executive the work at 1)% below estimate rate, 2) At estimate rate , 3)% above estimate rate | | | | | |
| | CONT | RACTOR | | ASS | SISTANT EXECUTIVE ENG | INEER |

Name :-

Address :-