

Quotation Notice

Sealed competitive quotations are invited from the manufactures, for the supply of the following item for the use in the Department of Computer Science, University of Kerala.

Sl. No.	Items with specification	Qty
1.	Supply, installation, testing and commissioning the following capacity of wall mounting, high energy efficient, single phase, inverter type, split air conditioner unit (IDU) having 5-star rating, fitted with hermetically sealed compressor (ODU) suitable for eco-friendly and energy efficient refrigerants R-32/R-410A, conforming to IS: 1391 Part-2 1992 (with latest amendments except power consumption norms) suitable for operation on 230V, 50Hz AC supply and capable of performing functions such as cooling, dehumidifying, air circulating, filtering etc. and having features of long distance piping flexibility, wide angle air flow, indoor noise level<43 dB as required. The condensing and evaporating coils should be made of copper tubes (100% copper) and a standard length of 3 meters of soft drawn bright annealed copper refrigerant pipes of suitable sizes should be supplied along with the AC unit for the function of suction and discharge and the copper pipes should be properly insulated with 10 mm thick closed cell Class O elastomeric nitrile rubberized foam sleeve insulation. A standard length of 3 meters of suitable size ISI marked flexible copper control cable for electrically connecting IDU and ODU of AC unit and microprocessor based cordless remote control with required number of suitable batteries should also be supplied along with the AC unit as required. There should be 3 numbers of free services for the AC unit for one year applicable from the date of commissioning. One year replacement warranty should be provided for the entire AC unit along with the PCB and 10 years exclusive warranty should be provided for the compressor. (Make: Panasonic, Voltas, Carrier, Bluestar or Daikin)	
a	2-Ton split type inverter AC (5-star rated)	3 Nos.
2.	Supply and providing extra length of superior quality soft drawn bright annealed copper refrigerant pipes (suction and discharge) of suitable sizes for extending the refrigerant piping between ODU and IDU of the AC unit and properly insulating the copper pipes with 10mm thick closed cell Class O elastomeric nitrile rubberized foam sleeve insulation including brazing, pressure check, leak testing etc. as required.	6 mtrs.
3.	Supply and drawing the following sizes of multi-core PVC insulated & FRLS PVC sheathed 650/1100V grade copper conductor round flexible cables conforming to IS 694 Part 1 1960 in the existing surface/recess conduit for electrically connecting IDU and ODU of the AC unit as required including giving necessary connections of the following sizes.	
a	3 core 4.00 sq.mm copper conductor round flexible cable	6 mtrs.
4.	Supply and fixing good quality of factory made powder coated MS frames (wall mounting brackets) using required numbers of suitable size anchor bolts for mounting the outdoor unit of AC in position along with anti vibration pads as required.	3 sets
5.	Supply, installation, testing and commissioning of wall mounting type 5KVA voltage stabilizer with input voltage range of 170 V - 270 V having features of high power efficiency, intelligent time delay system, Low & High voltage cut-off protection, built-in thermal overload protection, LED indications etc. suitable for single phase 2-Ton air conditioner unit. Warranty- 5 years. (Make: V-Guard, Crompton or Microtek)	3 Nos.
6.	Supply and Fixing the following modular switches & accessories in the existing front plates and giving necessary connections as required (RoHS complaint)	
a	16A 3-pin plug top	3 Nos.

Terms & Conditions:

1. Prices shall be quoted item wise with unit price and total price.
2. The price should be inclusive of all taxes, duties, transportation, installation etc. Nothing extra will be paid in addition to the quoted rate.
3. Validity of tender: Tender submitted shall remain valid at least for 90 days from the date of opening the tender. Validity beyond three months from the date of opening of the tender shall be by mutual consent.
4. Delivery and installation: Proposed delivery schedule should be mentioned clearly. Delivery and installation should be made at Dept. of Computer Science, University of Kerala, Kariavattom campus, Trivandrum - 695581, without any extra cost. Complete installation, testing and demonstration of the system and day-to-day maintenance are to be provided at site.
5. Service facility: Supplier should mention their details of service setup and manpower in Trivandrum who are responsible for after sales support.

The quotations should reach the “**Asst. Professor & Head, Department of Computer Science, University of Kerala, Kariavattom, Thiruvananthapuram – 695 581**” on or before **23-06-2020, 3:00 pm**.

Sd/-
Asst. Professor & Head
Dept. of Computer Science
University of Kerala