

UNIVERSITY OF KERALA**ENGINEERING UNIT, SUBDIVISION II, KARIAVATTOM****Quotation schedule for Urgent work for providing water connection and stainless steel sink in newly built iCEIB building at Kariavattom Campus.****Date of submission :****Time of Completion : 20 days**

SL No	Quantity	Description	Unit	Rate	Rate in Words	Amount
1	Civil Work					
1.01	16.000	10.28 Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.)	kg	784.84	Rs Seven hundred and eighty four Ps Eighty four only	12557.44
1.02	24.000	50.18.9.14.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 32 mm dia 10 Kgf/cm ² - External work- Exposed on wall	metre	372.38	Rs Three hundred and seventy two Ps Thirty eight only	8937.12

1.03	1.500	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc. 25 mm pipe 12 kgf/cm2	metre	510.51	Rs Five Hundred and Ten Ps Fifty one.	765.77
1.04	3.000	OD53823/2025-2026 Supplying and fixing 25x15 PN16 Elbow including jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge.	each	81.62	Rs Eighty one Ps Sixty two only	244.86
1.05	1.50	50.18.8.7.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work including cutting chases and making good the wall etc. 63 mm pipe 6 Kgf/cm2	metre	702.35	Rs Seven hundred and two Ps Thirty five only	1053.53
1.06	8.00	50.18.9.17.1 Providing and fixing PVC pipes including fixing the pipe with clamps/ clip at 1.00 m spacing . This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 63 mm dia 6 Kgf/cm2 - External work - Exposed on wall	metre	294.64	Rs Two hundred and ninety four Ps Sixty four only	2357.12

1.07	3.00	50.18.9.20.1 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes,including jointing with PVC solvent cement - 63 mm dia Elbow	no	78.81	Rs Seventy Eight Ps Eighty one only	236.43
1.08	3.000	50.18.9.20.2 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement -63 dia 45 degree Elbow	no	70.09	Rs Seventy Ps Nine only	210.27
1.09	3.00	50.18.9.20.3 Providing and fixing PVC moulded fittings /accessories for Rigid PVC pipes,including jointing with PVC solvent cement - 63 mm dia Door Elbow.	no	86.35	Rs Eighty Six Ps Thirty five only	259.05
1.1	2.00	50.18.9.20.5 Providing and fixing PVC moulded fittings/accessories for Rigid PVC pipes including jointing with PVC solvent cement - 63x63x63 mm dia Tee	no	92.31	Rs Ninety two Ps Thirty one only	184.62
1.11	3.000	17.10.2.1 Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required: Kitchen sink without drain board610x510 mm bowl depth 200 mm	each	5479.26	Rs Five Thousand Four Hundred and Seventy Nine Ps Twenty six only	16437.78

1.12	3.00	OD53837/2025-2026 Providing and fixing CP Swan neck tap of approved quality conforming to IS standard and weighing not less than 690 gms. 15 mm nominal bore.	each	1796.80	Rs One Thousand Seven Hundred and Ninety Six Ps Eighty only	5390.40
1.13	3.00	17.28.1.1 Providing and fixing P.V.C. waste pipe for sink or wash basin including PVC. waste fittings complete. Semi rigid pipe 32 mm dia	each	116.61	Rs One Hundred and Sixteen Ps Sixty One only	349.83
1.14	3.00	17.69.1 Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour, Waste Coupling 31 mm dia of 79mm length and 62 mm breadth weighing not less than 45 gms	each	132.04	Rs One hundred and thirty two Ps Four only	396.12
Total amount						49380.33
After round off Total (Rs.49,380/- Rupees Forty Nine Thousand Three Hundred and eighty Only)						

I/We undertake to execute the work at 1).....% below estimate rate

2) At the estimate rate

3) Above the estimate rate

CONTRACTOR (Name and Address)

Sd/-
ASSISTANT EXECUTIVE ENGINEER