UNIVERSITY OF KERALA

ENGINEERING UNIT, SUBDIVISION II, KARIAVATTOM

Civil work for providing concrete flooring at the rear side of Ac-REM STEM building at Kariavattom Campus.

Date of submission : **Time of Completion : 20 days**

SL No	Quanity	Description	Unit	Rate	Rate in Words	Amount
1	**A/C outdoor floor concrete**					
1.01	2.000	OD102739/2026-2027 Labour (coolie) engaged for de-weeding and leveling the existing earthen ground as per required slope for proper dissipation of rain water complete	each	1106.22	Rs Three hundred and sixty seven Ps Seventy Two only	2212.44
1.02	9.000	4.1.8 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	cum	8109.18	Rs One Thousand Six Hundred and Forty five Ps Thirty six only	72982.62
	Total amount					**75195.06**
	After round off Total (Rs.75,195/- Rupees Seventy Five Thousand One Hundred and Ninety Five Only)					

I/We undertake to execute the work at 1)…….% below estimate rate

2) At the estimate rate 3) …….. Above the estimate rate

Sd/-

CONTRACTOR (Name and Address)

ASSISTANT EXECUTIVE ENGINEER(i/c)