

UNIVERSITY OF KERALA**ENGINEERING UNIT**

Quotation Schedule for Providing aluminium Partition with a sliding door and carrying out cabinet maintenance in second floor room No BCH-51 at Department of Bio Chemistry at Kariyavattom Campus .

Date of submission-01/11/2026

Time of Completion -: 15 days

SL No	Quantity	Description	Unit	Rate	Rate in Words	Amount
1	13	15.41 Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead.	Sqm	59.63	Rs Rs Fifty Nine Ps Sixty Three only	775.19

2	55	<p>21.1.1.2 Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.(Glazing, paneling and dash fasteners to be paid for separately): For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)</p>	Kg	597.71	Rs Five Hundred and Ninety Seven Ps Seventy One Only	32874.05
3	33	<p>21.1.2.2 For shutters of doors, windows & ventilators including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber/ neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)</p>	Kg	723.98	Rs Seve Hundred and twenty Three Ps Ninety Eight only	23891.34

4	4.5	21.3.1 Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer - in -Charge. (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	Sqm	1307.23	Rs One Thousand and Three Hundred and Seven Ps Twenty Three only	5882.54
5	13.500	OD87177/2026-2027 Providing and fixing 3mm thick ACP sheet, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer - in- Charge	M2	1002.60	Rs One Thousand and Two Ps: Sixty Only	13535.10
6	2	9.100.1 Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete:125 mm	Nos	76.98	Rs Seventy Six Ps Ninenty Eight Only	153.96
7	10	9.165.3 Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete.75 mm	Nos	62.76	Rs Sixty Two Ps Seventy Six Only	627.60

8	20	Supplying and providing auto closer soft closing hinges of approved quality for cupboard shutters with screws etc complete as per direction of engineer in charge Data for 10 no	Each	302.37	Rs Three Hundred and Two Ps Thirty Seven Only	6047.40
		Total				83787.18
		After round off Total				83787/-

I/We undertake to execute the work at 1.....% below estimate rate

2) At the estimate rate 3) Above the estimate rate

CONTRACTOR (Name and Address)

Sd/-
Assistant Executive Engineer (i/c)