

Schedule

UNIVERSITY OF KERALA						
SUB DIVISION I, KARIYAVATTOM						
Re Quotation schedule for the Urgent maintenance work in AcH section in the University Health Centre building at SH Campus - Reg.						
Date of Submission :- 08/07/2025				Time of duration :- 30 days		
Sl No	Quantity	Description of item	Unit	Rate	Rate in words	Amount
1	2.00	Labour engaged for removing existing damaged table from the office as per the direction of Engineer in Charge	Each	1106.22	One thousand one hundred and six Rupees and twenty two paise only	2212.44
2	12.60	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dashfasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc.Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminnium snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.(Glazing, paneling and dash fasteners to be paid for separately): For fixed portionPowder coated aluminium (minimum thickness of powder coating 50 micron)	Kg	597.71	Five hundred and ninety seven Rupees and seventy one paise only	7531.15
3	8.400	For shutters of doors, windows & ventilators including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber/ neoprene gasket required (Fittings shall be paid for separately)Powder coated aluminium (minimum thickness of powder coating 50 micron)	Kg	723.98	Seven hundred and twnty three Rupees and ninety eight paise only	6081.43

Schedule

4	6.00	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete:100 mm	Each	68.25	Sixty eight Rupees and twenty five paise only	409.50
5	1.00	:Supplying chemical emulsion in sealed containers including delivery specified.<be>Imidacloprid 30.5% (TATA-Termix). chemical emulsion in sealed containers including delivery specified.Imidacloprid 30.5% (TATA-Termix)	Litre	4500.33	Four thousand five hundred Rupees and thirty three paise only	4500.33
6	41.760	:Diluting and injecting treatment of existing building floors (plinth area of the building outside and inside floors) using dilute chemical emulsion, including drilling 12mm diameter holes and plugging with cement mortar 1;2 to match the existing floor-Imidacloprid 30.5%(TATA-Termix).Based on 2.35.3 Diluting and injecting treatment of existing building floors (plinth area of the building outside and inside floors) using dilute chemical emulsion, including drilling 12mm diameter holes and plugging with cement mortar 1;2 to match the existing floor- Imidacloprid 30.5%(TATA-Termix).	M2	319.08	Three hundred and nineteen Rupees and eight paise only	13324.78
7	15.720	Providing and fixing 3mm thick ACP sheet, in paneling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer - in- Charge	M2	1002.60	One thousand and two Rupees and sixty paise only	15760.87
Total Amount						49821
Rs 49,821 /- (Rupees :- Forty nine thousand eight hundred and twenty one only)						
I/We agreed to executive the work at 1).....% below estimate rate, 2) At estimate rate , 3).....% above estimate rate						
CONTRACTOR			ASSISTANT EXECUTIVE ENGINEER			

Name :-

Address :-