

Schedule

UNIVERSITY OF KERALA						
SUB DIVISION I, KARIYAVATTOM						
Quotation schedule -Women's Hostel Thycaud – Repair and maintenance of car porch and front yard						
Date of Submission :- 12/08/2025				Time of duration :- 20 days		
Sl No	Quantity	Description of item	Unit	Rate	Rate in words	Amount
1	2.570	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 meters lead: With cement mortar 1:4 (1 cement : fine sand)	M2	592.62	Five hundred and ninety two Rupees and sixty two paise only	1523.03
2	9.300	Cleaning of reinforcement from rust from the reinforcing bars to give it a total rust free steel surface by using alkaline chemical rust remover of approved make with paint brush and removing loose particles after 24 hours of its application with wire brush and thoroughly washing with water and allowing it to dry, all complete as per direction of Engineer-In-Charge. Bars upto 12 mm diameter	M	8.53	Eight Rupees and fifty three paise only	79.33
3	2.570	Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specifications and direction of Engineer-In-charge complete in all respect. SBR Polymer (@10% of cement weight) modified cementitious bond coat @2.2 kg cement per sqm of surface area mixed with specified proportion of approved polymer	M2	150.91	One hundred and fifty Rupees and ninety one paise only	387.84

Schedule

4	35.750	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	M2	57.76	Fifty seven Rupees and seventy six paise only	2064.92
5	35.750	Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying : a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/sqm. This layer will be allowed to air cure for 4 hours. b) Second layer of slurry of cement @ 0.242 kg /sqm mixed with water proofing cement compound @ 0.126 kg/sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry.	M2	662.24	Six hundred and sixty two Rupees and twenty four paise only	23675.08
6	35.750	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:3 (1 cement : 3 fine sand)	M2	479.64	Four hundred and seventy nine Rupees and sixty four paise only	17147.13
7	1.750	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	M3	8109.18	Eight thousand one hundred and nine Rupees and eighteen paise only	14191.07

Schedule

8	0.875	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	M3	9441.22	Nine thousand four hundred and forty one Rupees and twenty two paise only	8261.07
Total Amount						67329
Rs 67,329 /- (Rupees :- Sixty seven thousand three hundred and twenty nine only)						
I/We agreed to execute the work at 1).....% below estimate rate, 2) At estimate rate , 3).....% above estimate rate						
CONTRACTOR			ASSISTANT EXECUTIVE ENGINEER			

Name :-

Address :-