

UNIVERSITY OF KERALA**ENGINEERING UNIT SUBDIVISION1**

Quotation scheduled for Repair to roof and ceiling in rooms GER-08 and ENG -09 in the Institute of English building at SH Campus .

Date of Submission 07/08/2025**TOC 15 days**

SL No	Quantity	Description	Unit	Rate	Rate in Words	Amount
1	11	15.28.1 Dismantling roofing including ridges, hips, velleys and gutters etc., and stacking the material within 50 metres lead of :G.S. Sheet	M2	174.31	Rs One Hundred Seventy Four Ps Thirty One Only	1917.41
2	5	OD40142/2025-2026 Carpenter engaged for fixing and repairing the roof top and ceiling	Each	1224.56	Rs One Thousand Two Hundred Twenty Four Ps Fifty Six only	6122.80
3	14	OD98913/2025-2026 :Removing and re-adjusting MP roofing tiles	M2	122.53	Rs One Hundred Twenty Two Ps Fifty Three only	1715.42
4	2.5	OD36259/2025-2026:Removing and re-adjusting MP ridge and hip tiles	Mtr	233.63	Rs Two Hundred Thirty Three Ps Sixty Three	584.08
5	0.156	50.9.14.1 Supplying and fixing Anjily wood reapers of size 50x25 mm with wire nails including cost and conveyance of materials etc. complete.	M3	106816.68	Rs One Lakh Six Thousand Eight Hundred Sixteen Ps Sixty Eight Only	16663.40

6	0.098	50.9.13.1 Supplying and fixing Anjily wood wrought and put up for roof members including cost and conveyance of materials etc. complete .	M3	91466.39	Rs Ninty one Thousand Four Hundred Sixty Six Ps Thirty Nine Only	8963.71
7	25	OD98881/2025-2026 Supplying first class M P Tiles 320 mm	Nos	41.53	Rs Fourty One Ps Fifty Three Only	1038.25
8	11	OD97865/2025-2026 Roofing with Departmental M P Tiles 320 mm or nearest available size	M2	85.79	Rs Eighty Five Ps Seventy Nine Only	943.69
9	5	OD98898/2025-2026 Supplying MP hip and ridge tiles of nearest available size instead of damaged one	Nos	70.56	Rs Seventy Ps Fifty Six only	352.80
10	2	OD97867/2025-2026 Roofing with departmental M P hip and ridge Tiles of nearest available size in cement mortar 1:3	Mtr	198.44	Rs One Hundred Ninty Eight Ps Fourty Four	396.88
11	1	13.1.1 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	M2	377.98	Rs Three Hundred Seventy Seven Ps Ninty Eight	377.98
12	4	50.9.16.2 Ceiling 12 mm Anjili wood planks, planed lap jointed and wire nailed to rafters and collars including all cost of materials labour charges etc complete	M2	1638.76	Rs One Thousand Six Hundred Thirty Eight Ps Seventy Six Only	6555.04

13	22	12.26.1 Providing and fixing plain multipurpose cement board(Hight pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid	M2	991.39	Rs Nine Hundred Ninty One Rs Thirty Nine Only	21810.58
14	30	13.48.2 Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications:Painting wood work with Deluxe Multi Surface Paint	M2	185.73	Rs One Hundred Eighty Five Ps Seventy Three only	5571.90
	Total					73013.93
	After round off Total (Rs 73014/- Seventy Three Thousand Foutreen Only)					

1)Above the Estimate rate

2) Below the Estimate rate

3) At the Estimate rate

CONTRACTOR (Name and Address)

ASSISTANT EXECUTIVE ENGINEER