UNIVERSITY OF KERALA

ENGINEERING UNIT, SUBDIVISION II, KARIAVATTOM

Urgent work for installation of steel gate at the entrance of toilet/ wash area at new building for MA Economics, Kariavattom.

Date of submission : **Time of Completion : 15 days**

SL No	Quanity	Description	Unit	Rate	Rate in Words	Amount
1	**Steel gate**					
1.01	86.000	10.16.1 Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc.complete.Hot finished welded type tubes	kg	198.59	Rs One hundred and Ninety eight Ps Fifty Nine only	17078.74
1.02	1.500	15.56 Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	679.34	Rs Six Hundred and Seventy nine Ps Thirty four only	1019.01
1.03	8.000	13.61.1 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	sqm	168.52	Rs One Hundred and Sixty Eight Ps Fifty two only.	1348.16
	Total amount					**19445.91**
After round off Total (Rs.19,446/- Rupees Nineteen Thousand Four Hundred and Forty six Only)						

I/We undertake to execute the work at 1)…….% below estimate rate

2) At the estimate rate 3) …….. Above the estimate rate

Sd/-

CONTRACTOR (Name and Address) ASSISTANT EXECUTIVE ENGINEER(i/c)