



UNIVERSITY OF KERALA

Thiruvananthapuram, Kerala, India – 695034

(Established as University of Travancore by the Travancore University Act in 1937 and reconstituted as University of Kerala by the Kerala University Act of 1957 and presently governed by the Kerala University Act of 1974 passed by the Kerala State Legislative Assembly)
(Re-accredited by NAAC with A++ Grade)

Ad B II/03/2458/2025

Quotation Notice

Competitive quotations are invited from interested vendors within Kerala towards supply and installation of CCTV system with sound recording facility in the Senate Chamber at University of Kerala, Palayam.

1	Name of work /Items	Supply and Installation of CCTV system with sound recording facility in the Senate Chamber at University of Kerala, Palayam
2	Quotation No.	Ad B II/03/ 2458 /2026
3	Period of Completion	45 Days
4	Last Date of receipt of quotation	25.05.2026 3.00 pm
5	Date and time of Opening quotation	25.05.2026 3.30 pm
	Contact details for	Instrumentation Engineer, CLIF, Kariavattom



6	Technical Clarification	Campus, University of Kerala. Ph: 2308566
---	----------------------------	--

Specifications appended as Annexure A

Terms and Conditions

1. The vendor shall quote price in clear terms. The rates quoted must be inclusive of all taxes, cost of supply at site, warranty and installation charges etc. The price should be quoted only in Indian rupees.
2. Intending vendors should send their quotations so as to reach the officer mentioned in the quotation notice, on or before the due date and time noted therein. No quotation received after the specified date and time will be accepted on any account.
3. The quotations will be opened on the appointed day and time in the office of the Registrar, in the presence of such of those vendors or their nominees who may be present at that time.
4. Complaints with the items supplied should be rectified/replaced to the satisfaction of the University by the suppliers at their own cost.
5. The vendors shall undertake to supply materials according to the specifications (appended as Annexure A)
6. No representation for enhancement of rates once accepted will be considered.
7. Validity: - The Bid will be valid for 90 days from its date of opening. Further extension can be done by mutual consent.
8. Delivery :- The item should be delivered at the Senate Chamber, Senate House Campus.
9. Installation and Commissioning: The items shall be installed and commissioned in the Senate Chamber, Senate House Campus.

Period of Completion:- The work shall be completed within a period 45 days from date of issue of supply order.

10. Payment:- The University will release the payment only after inspecting the work and satisfy that the items are supplied as per the requirements and on the basis of actual quantity executed. The payment will be made after successful completion of the supply on producing invoice in triplicate. The final bill shall be based on the actual quantity of supply made.
11. Warranty/Guarantee: The guarantee/ warranty of the items shall be specified in the quotation. Corresponding model of items Sl.No: 1,2,3,4 & 6 should have a OEM warranty period of minimum 2 year. The supplier shall guarantee to repair/replace the items or its part if found defective within the warranty (Defect Liability) period mentioned in Specification/ estimate.
12. Attach the STQC ER Certificate for the corresponding model of CCTV Camera
13. In case of dispute arises, the decision of University authority shall be final.
14. The undersigned reserves the right to reject or accept any or all the



quotations received fully or partly without assigning any reason thereof.

15. General rules relating to purchase of materials/equipment mentioned in store purchase manual will be also applicable to this quotation.

The quotations should be addressed to the **Registrar, University of Kerala, Senate House Campus, Palayam, Thiruvananthapuram - 695034** in a sealed cover with the quotation number and name - Supply and Installation of CCTV system with sound recording facility in the Senate Chamber duly superscribed on the cover.

08.05.2026

REGISTRAR



Annexure - A

Proposed locations

1. Proposed Camera Locations in the Senate Chamber:
 - a. Two cameras on the left and right sides of the projection board, facing the members.
 - b. One camera on the left side of the projection board, facing the members.
 - c. One ceiling-mounted camera facing the Chair.
2. The network rack, PoE switch, and UPS shall be installed in the audio console room.
3. The NVR shall be installed in the existing rack near the Vice Chancellor’s Chamber. The camera display shall be provided on the TV installed in the Vice Chancellor’s Chamber.

Estimate for the supply and Installation of CCTV system in the Senate Chamber with sound recording facility - SH Campus Palayam								
Sl. No.	Item	Qty	Make	Model	Rate	GST (%)	GST amount	Total Amount
Passive/Active Components								
1	8 Channel Professional Rack mountable Network Video Recorder with 8 Channel IP Camera input Instastream, H.265, H.264, MJPEG Up to 12 MP resolution preview and playback Incoming bandwidth: 160 Mbps, ONVIF protocol, Should Support 2 SATA interface up to 10 TB or better for 1 HDD, 2 USB ports(2.0) HDMI / VGA simultaneous video output The Item should comply STQC (certification).	1No						



2	4 MP or better Fixed IP, IR Bullet Camera 1/2.9" CMOS Image Sensor, 4MP (2688 × 1520)@1-25/30fps/ (2560 × 1440)@1-25/30, Instastream, H.265, H.264, H.264H, H.264B, MJPEG, Support WDR (120dB), Day/Night, 3D NR, ROI, AWB, AGC, BLC, HLC, IR Range of 30 Mtr., Warm Light Range of 30 Mtr. 3.6mm fixed Lens, Support Built-in Mic, PoE, IP67 The Item should comply STQC (certification).	4 No					
3	10-Port Ethernet Switch with 8-Port PoE and Giga Uplink ports Preferred Make: HP/Netgear/ TP-Link/Allied Telesis	1 No					
4	Surveillance HDD for minimum 20 days backup - 4 TB or better Preferred Make: Seagate/ Western Digital	1 No					
5	2U wall mount Network rack with accessories (Netrack/ Rittal/Dlink or equivalent)	1 No					
6	1 KVA UPS (Double battery, backup for minimum 20 minutes) with suitable wall mount stand (light weight preferred) (APC/V Guard/Hykon)	1 No					



7	Cat6 UTP Cable (Molex/ Panduit/ Commscope)	275 Mtr							
8	3/3 SMB (Camera box)	4 No							
9	RJ 45 Connectors with Strain Relief Boot	12 No							
10	20mm White ISI PVC Pipe with accessories	130 Mtr.							
11	25mm White ISI PVC Pipe with accessories	25 Mtr.							
12	HDMI Cable of 10 Mtr length (High Speed, 4K resolution)	1 No.							
13	USB Extension Cable of 5 Mtr length	1 No.							
Labour									
14	Fixing and configuration of 8 CH NVR	1 No							
15	Fixing and configuration of bullet camera	4 No							
16	Cat6 UTP Laying Charges	275 Mtr.							
17	RJ 45 / IO Termination Charges	12 No							
18	20mm/25mm/32mm PVC Pipe Laying Charges through surface	155 Mtr							



19	Fixing of Wall mountable network rack	1 No							
20	Installation of 1 KVA UPS	1 No							
21	Wiring Electrical point (With 2 switches and two 6A plug Point) if necessary	1 No							
22	Testing, Commissioning and Labeling	1 Job							
Total									

