

**UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM.**

**TENDER SCHEDULE FOR URGENT CIVIL WORKS FOR ACCOMMODATING IMK IN THE IDE BUILDING AT KARIAVATTOM
CAMPUS**

Date of Tender: 23.10.2013

Time of Completion: 3 months

Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1	120m ²	Supplying fabricating and fixing aluminium powder coated partition using section of size 100x45x50x1.85mm (9246) @ 1.50 kg/M for bottom, horizontal frame and 62.50x37.10x1.50mm (9238 @ 0.885 kg/m) for around frames vertical and horizontal except bottom frame and 62.50x37.10x1.50mm (9237 @ 0.905 kg/m) for intermediate frames verticals and horizontals and providing 12mm thick pre-laminated top panels fixed with glazed top of size 19.70x17.70x0.90mm (4682 @ 0.113 kg/m) on both side including 'L' angle at covers and steel screws and all cost of materials labour charges etc. complete.	M ²	2087.00	Rs. Two thousand & eighty seven	250440/-
2	9M ²	Supplying fabricating and fixing aluminium power coated door shutter using section of size 100x44.50x1.85mm (9246 @ 1.504kg/m for bottom horizontal frame and 55.44.50x1.50mm (9284 @ 0.790 kg/m for top horizontal frame and 50.44.50x1.50mm 9286 @ 0.905 kg/m for middle frame and providing 12mm thick pre-laminated sheet for bottom quarrel and 5.50mm thick plain glass panes, top panel fixed with glazed chip 19.70x0.90mm (4682 @ 0.113 kg/ on both side and all fittings such as 2 Nos. pivot 2 Nos. Door handle, 1 No. lock, 1 No. door closer etc. including "L" angle screws, rubber beading etc. complete.	M ²	4570.00	Rs. Four thousand five hundred & seventy	41130/-
3	90M ²	Supplying and fixing false ceiling using aluminium powder coated 'L' angle of size 25.40x25.40x1.10mm (1767) for around frame and 25x25x1.27mm (3135) T section for intermediate jointing and providing anodized aluminium square tube of size 24x24x1.20mm (9810) at 60cm c/c hanging with G.I wire and	M ²	827.00	Rs. Eight hundred & twenty seven	74430/-

		fixed with 7.50mm thick PVC panel board with steel screws to the frame in correct time and level including all cost of materials and labour and scaffolding charges etc. complete.				
4		Supplying and making computer table (120x60x75cm) using twin laminated particle board including drawers, cupboard etc. as per drawing and direction of depl. Authorities.	LS			7000/-
5	2 Nos.	Making shelf/Rack (150x45x150cm) using twin laminated sheet as per drawing & direction of depl. authorities	E	12000.00	Rs. Twelve thousand	24000/-
6	9 Nos.	Making teaching desk (200x60x75cm) using twin laminated sheet one end with drawyer and cubpard etc. as per drawing and direction of depl. Authorities.	E	8000.00	Rs. Eight thousand	72000/-
7	9 Nos.	Supplying and fixing white board and marker standard (small type) board size (200x150cm)	E	5000.00	Rs. Five thousand	45000/-
8	4 Nos.	Constructing new toilet (150x120cm)x60cm) including all items for brick work 60cm height plastering concrete wall tiles floor tiles trap EWC with flush CP fittings for tap and PVC pipe & fittings etc. complete	LS			90000/-
9	4 Nos.	Making aluminium partition with door for toilets using alu. Section and 10mm thick iron panel of pre-laminated.	LS			92000/-
		TOTAL				6,96,000/-

Rs.6,96,000/- (Rupees Six Lakh & ninety six thousand only)

I/We agree to execute the work. 1.percentage above the estimate rate.

2.percentage below the estimate rate. 3. At the estimate rate.

UNIVERSITY ENGINEER

CONTRACTOR