

**UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM**

**TENDER SCHEDULE FOR THE CONSTRUCTION OF NEW BADMINTON COURT EXCLUSIVE FOR
UCE STUDENTS AT KARIYAVATTOM**

Date of Tender: 23.10.2013

Time of completion: 2 months

No	Quantity	Description	Unit	Rate	Rate in words	Amount
1.	225m ²	Clearing grass and other vegetation and small trees of girth up to 30cms including rooting out and removing of debris to a distance of 150M etc.	100M ²	217.00	Rs. Two hundred and Seventeen	488/-
2.	105M ²	Earth work for forming the surface of court by levelling undulations if any, sectioning up to 150mm removing excess earth etc. and levelling the ground evenly as per deptl. directions.	10M ²	216.80	Rs. Two hundred and Sixteen & Ps. Eighty	2276/-
3.	15000dm ³	Cement concrete 1:2:4 using 20mm broken stone including watering curing etc. complete	10dm ³	73.30	Rs. Seventy three & Ps. Thirty	109950/-
4.	5500dm ³	Cement concrete 1:2:4 using 12mm broken stone including watering curing etc. complete	10dm ³	73.85	Rs. Seventy three & Ps. Eighty five	40618/-
5.	105M ²	Plastering with cement mortar 1:3, 12mm thick one coat floated hard and trowelled smooth	10M ²	2124.00	Rs. Two thousand one hundred and twenty four	22302/-
6	110M	Painting with sy. Enamel paint (mat finish, approved quality & colour) for marking lines in the court 4cm wide as per departmental direction	10M	155.00	Rs. One hundred and fifty five	1705/-

7	2 Nos.	Supplying and fixing 75mm GI pipe for the post of Badminton court with a height of 1.55M from the floor level 45cm anchoring length (total length of pipe 2.20M) including court thickness) and fixed on ground with cement concrete 1:4:8, 40mm broken stone in 45x45x45cm pit including charges for necessary earthwork, 2 Nos. 15cm GI pipe for horizontal anchoring to avoid tilting, 2 Nos. 12mm M.S rod for providing hooks, welding and fabrication charges, painting priming coat with zinchromate primer and two coat of synthetic paint in black and white colour alternately each strip having 20cm in length etc. complete.	E	1835.00	Rs. One thousand Eight hundred and Thirty five	3670/-
		Total				1,81,009/-

PAC Rs. 1,81,009/- (Rupees One lakh eighty one thousand and nine only)

I We agreed to execute the work. 1.percentage above the estimate rate.
2.percentage below the estimate rate. 3. At the estimate rate.

UNIVERSITY ENGINEER

CONTRACTOR