

UNIVERSITY OF KERALA						
ENGINEERING UNIT, SUBDIVISION II, KARIAVATTOM						
Quotation schedule for urgent work for providing entrance way at staff quarters C06 at Kariavattom Campus.						
Date of Quotation : 10/10/2025				Time of Completion : 15 days		
SL No	Description	Quantity	Unit	Rate	Rate in Words	Amount
1	2.1.1 Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5m in width as well as 10 sqm on plan including disposal of excavated earth up to 50 m and lift up to 1.5 m, disposed soil to be levelled and neatly dressed:All Kinds of soil	27.00	sqm	137.18	Rs One Hundred and thirty seven Ps Eighteen only	3703.86
2	4.1.6 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 40 mm nominal size derived from natural sources)	2.60	cum	8550.44	Rs Eight Thousand Five Hundred and Fifty Ps Forty four only	22231.14
3	13.18 Neat cement punning	21.00	sqm	86.91	Rs Eighty Six Ps Ninety one only	1825.11
Total Amount						27760.11
After round off Total (Rs.27,760/- Twenty seven Thousand Seven Hundred and Sixty Only)						27760.00

I/We undertake to execute the work at 1).....% below estimate rate

2) At the estimate rate

3) Above the estimate rate

CONTRACTOR (Name and Address)

Sd/-
ASSISTANT EXECUTIVE ENGINEER